

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20045-0000

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1967
10-16-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Ben B. Tepper,
Complete Address 7751 CARONDELET AVE. CLAYTON, MISSOURI 63105
830 North Mission, Wichita, Kansas.
Lease Name Niblock Well No. 2
Location Appr. CS/2-SE-NW Sec. 2 Twp. 8 Rge. (E) (W) 26
County Sheridan Total Depth 4173
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated

Plugging Contractor Paine Drilling, Incorporated,
Address Box "D", Hill City, Kansas. License No.
Operation Completed: Hour 9:00PM Day 9 Month 10 Year 1967

The above well was plugged as follows:

220'--7" OD Surface pipe, cement circulated with 125 Sx. (6 1/2" hole).
Dakota section from 835' to 1000'.

Circulated hole with heavy mud. Pulled DP to 1020' and displaced 55 Sx. cement thru
DP from 1020' to 720'. Pulled DP to 240' and displaced 15 Sx. cement thru DP from
240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement from
40' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. S. Dechels
Well Plugging Supervisor

DATE 10/16/67
INV. NO. 6504-u