

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20068-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 24 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Paine Drilling, Incorporated,

Complete Address: Box "D", Hill City, Kansas.

Lease Name Andregg Well No. 2

Location NE-NW-SW Sec. 2 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3885'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company, Incorporated.

Address: Box #364, Great Bend, Kansas. License No. 9

Operation Completed: Hour 5:30 PM Day 20 Month 12 Year 1968

The Above well was plugged as follows:

211'--7" OD Surface casing, cement circulated. (6 1/2" Hole).
3871'--4 1/2" Production casing cemented on bottom with 75 Sx. Top of cement @ 3200'--
(Temp. Surv.). Top of Dakota section @ 1015'.

Sanded well back to 3850' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing and
squeezed well with initially 5 sacks hulls and 7 sacks gel and followed with 75 Sx.
cement from 1240' to 900' then 10 sacks gel from 900' to 240' and followed with 15 Sx.
cement from 240' to 180' then 3 sacks gel from 180' to 30' and finally 10 Sx. cement
from 30' to bottom of cellar. Maximum pump-in pressure- 300#. Final shut-in pressure-
200#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols
Well Plugging Supervisor

DATE 12-24-68

INV. NO. 9095-W

12-24-68