

KANSAS

*P*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20031-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 31 1967  
7-31-67  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita Ave., Russell, Kansas.

Lease Name Niblock Well No. 1

Location CE/2-SE-<sup>NE</sup>~~SW~~ Sec. 3 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3935'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 3:30AM Day 26 Month 7 Year 1967

The Above well was plugged as follows:

225'--8 5/8" Surface pipe, cement circulated with 140 Sx.  
Dakota section from 1500' to 1675'.

Circulated hole with heavy mud, pulled DP to 1700' and displaced plug  
thru DP from 1700' to 1400' with 100 Sx. cement. Pulled DP to 240' and  
displaced plug thru DP with 20 Sx. cement. Pulled DP, set bridge with  
1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Pecher  
Well Plugging Supervisor

DATE 7/31/67  
INV. NO. 6041-W