

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20138-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

9-26-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Leo J. Dreiling & D. G. Hansen,

Complete Address: Victoria, Kansas.

Lease Name Albers Well No. 1

Location SE-SE-NE Sec. 5 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 4006'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No.     

Operation Completed: Hour 10:30PM Day 22 Month 9 Year 1968

The Above well was plugged as follows:

201'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 1100'

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 100 Sx. cement thru  
DP from 1325' to 1000'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from  
210' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Dehler  
Well Plugging Supervisor

INVOICED  
DATE 9/26/68  
INV. NO. 8516-W