

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1967

10-23-67

CONSERVATION DIVISION
Wichita, Kansas

15-179-20049-0000

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address Victoria, Kansas.

Lease Name Cass Well No. 1

Location SE-NW Sec. 6 Twp. 8 Rge. (E) (W)26

County Sheridan Total Depth 4080'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling and Sons, Incorporated,

Address Victoria, Kansas. License No.

Operation Completed: Hour 1:30PM Day 16 Month 10 Year 1967

The above well was plugged as follows:

199(--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 2090' to 1930'.

Circulated hole with heavy mud. Pulled DP to 2110' and displaced 100 Sx. cement thru
DP. from 2110 to 1790'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from
210 to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Deibel
Well Plugging Supervisor

INVOICED

DATE 10/23/67

INV. NO. 6540-0