

KANSAS

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 28 1972
CONSERVATION DIVISION
Wichita, Kansas

1-28-72

15-179-20299-0000

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name I. O. Miller and John O. Farmer, Incorporated,

Complete Address Box #352, Russell, Kansas.

Lease Name Pratt Well No. 1

Location CNE-SW Sec. 13 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3870'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor John O. Farmer, Incorporated,

Address Box #352, Russell, Kansas. License No.

Operation Completed: Hour 9:30 PM Day 25 Month 1 Year 1972

The above well was plugged as follows:

202'--8 5/8" Surface casing, cement circulated with 140 Sx.
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 110 Cu. Ft. cement
thru DP from 1150' to 825'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 1-28-72
INV. NO. 5095-W