

KANSAS

gl
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20355-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1973

CONSERVATION DIVISION
Wichita, Kansas

628-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Don E. Pratt,

Complete Address Box #370, Hays, Kansas.

Lease Name Irene B. Davis Well No. 2

Location SW-NW-NE Sec. 14 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3890'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 11:45 AM Day 26 Month 6 Year 1973

The above well was plugged as follows:

168'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 110 Cu. Ft. cement
thru DP from 1175' to 850'. Pulled DP to 185' and displaced 30 Cu. Ft. cement thru
DP from 185' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *R. L. Nichols*
Well Plugging Supervisor

DATE 6/28/73
INV. NO. 9569-W