

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20376-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 1 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
2-1-74

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Don E. Pratt,

Complete Address P. O. Box #370, Hays, Kansas.

Lease Name Irene B. Davis Well No. 3

Location SE-NE-SW Sec. 14 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3860'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Muffin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.       

Operation Completed: Hour 9:00 PM Day 27 Month 1 Year 1974

The above well was plugged as follows:

133'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 110 Cu. Ft. cement  
thru DP from 1175' to 850'. Pulled DP to 155' and displaced 30 Cu. Ft. cement thru  
DP from 155' to 80'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Daniels  
Well Plugging Supervisor

DATE 2/1/74

INV. NO. 8493-W