

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

15-79-30007-00-00

AUG 20 1965

CONSERVATION DIVISION  
Wichita, Kansas  
8-20-65

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Donald C. Slawson  
Complete Address: 408 One-Twenty Building, Wichita, Kansas  
Lease Name Pratt Well No. B-1  
Location CW/2-SE/SE Sec. 14 Twp. 8 Rge. (E) (W) 26  
County Sheridan Total Depth 3686  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A      X  
Other well as hereafter indicated:       
Plugging Contractor: Above  
Address:      License No.       
Operation Completed: Hour 7:15AM Day 18 Month 8 Year 1965

The Above well was plugged as follows:

251'--8 5/8" Surface pipe, cement circulated with 200 Sx.  
Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx. cement  
thru DP. Heavy mud to 240', set plug with 1/4 sack hulls and displaced 20  
Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10  
Sx. cement to bottom of cellar.

(Cementing operations performed by United Cementers)

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED  
DATE 8/20/65  
INV. NO. 1661-W