

KANSAS

*RP*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20102-0000

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas

5-27-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Company, Inc.,

Complete Address: 1425 Wichita Plaza, Wichita, Kansas.

Lease Name McKinney Well No. 1

Location CNE-NW Sec. 13 Twp. 8 Rge. (E) (W) 28

County Sheridan Total Depth 4075

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated:       

Plugging Contractor: Above

Address:        License No.       

Operation Completed: Hour 8:15PM Day 21 Month 5 Year 1968

The Above well was plugged as follows:

238'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
Top of Dakota section @ 1200'.

Circulated hole with heavy mud. Pulled DP to 1320' and displaced 100 Sx. cement thru  
DP from 1320' to 1000'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from  
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. B. Dehals*  
Well Plugging Supervisor

INVOICED

DATE 5/27/68  
INV. NO. 7810-11