

*14*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

*15-179-20078-00-00*

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 12 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
*3-12-68*

Operator's Full Name Dean & Clark, Incorporated,

Complete Address: 416 Union Center Building, Wichita, Kansas.

Lease Name Schaffer Well No. 1

Location CS/2-SE-SE Sec. 26 Twp. 8 Rge. (E) (W) 28

County Sheridan Total Depth 4102

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 11:15 PM Day 9 Month 3 Year 1968

The Above well was plugged as follows:

248'--8 5/8" Surface pipe, cement circulated.

Circulated hole with heavy mud. Pulled DP to 1800' and displaced 100 Sx. cement thru DP  
from 1800' to 1475'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from 245'  
to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. D. Nichols*  
Well Plugging Supervisor

DATE *3/12/68*

INV. NO. *7404-u*