

15-179-20173-00-00

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1969
CONSERVATION DIVISION
Wichita, Kansas
1/13/69

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name K. Clark Well No. 1

Location NW-NW-NE Sec. 32 Twp. 8 Rge. (E) (W) 28

County Sheridan Total Depth 3810'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 3:00 PM Day 8 Month 1 Year 1969

The Above well was plugged as follows:

250'--7" O D Surface casing, cement circulated with 100 Sx. (6 1/4" Hole).
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1310' and displaced 65 Sx. cement thru
DP from 1310' to 985'. Pulled DP to 275' and displaced 15 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. F. Finkel
Well Plugging Supervisor

INVOICED

DATE 1/14/69
INV. NO. 9197-W