

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20140-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1973
CONSERVATION DIVISION
Wichita, Kansas
11-19-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson,
Complete Address 408 One-Twenty Building, Wichita, Kansas.
Lease Name Shaw Well No. C-1
Location CSE-SE Sec. 33 Twp. 8 Rge. (E) (W) 28
County Sheridan Total Depth 4050'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Rockhold Engineering, Incorporated,
Address Box #695, Great Bend, Kansas. License No. 670
Operation Completed: Hour 12:00 M Day 16 Month 11 Year 1973

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 175 Sx.
4049'--4 1/2" Production casing cemented with 175 Sx. Well plugged back to 4016'. Top perforations from 3785' to 3788'.
Pushed plug to 3750', sanded back to 3700' and set 5 Sx. cement with dump bailer.
Pulled 4 1/2" casing (1227') and squeezed well initially with 5 sacks hulls and 9 sacks gel and followed with 110 Cu. Ft. cement from 1325' to 1000', then 19 sacks gel from 1000' to 240' and followed with 30 Cu. Ft. cement from 240' to 165' then 3 sacks gel from 165' to 45' and finally 10 Cu. Ft. cement from 45' to bottom of cellar.
(Mudding and cementing operations performed by Allied Cementing Company Incorporated).

I hereby certify that the above well was plugged as herein stated.

DATE 11/20/73

INV. NO. 8191-W

Signed: H. L. Nichols
Well Plugging Supervisor