

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20219-0000

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Vannocker & Ropfogel,

Complete Address 515 Sutton Place, Wichita, Kansas.

Lease Name Shaw Well No. 1

Location CNW-SE Sec. 33 Twp. 8 Rge. (E) (W) 28

County Sheridan Total Depth 4100'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor B. & B Drilling, Incorporated,

Address 548 Petroleum Building, Wichita, Kansas. License No.

Operation Completed: Hour 12:30 PM Day 19 Month 7 Year 1969

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1180'.

Circulated hole with heavy mud. Pulled DP to 1400' and displaced 100 Sx. cement thru
DP from 1400' to 1075'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1969

I hereby certify that the above well was plugged as herein stated.

INVOICED

CONSERVATION DIVISION
Wichita, Kansas

Signed: N. S. Dechels
Well Plugging Supervisor

DATE 7/23/69

7-23-69

INV. NO. 142-W