

KANSAS

M

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20230-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Shaw Well No. C-2

Location CSE-NW Sec. 33 Twp. 8 Rge. (E) (W) 28

County Sheridan Total Depth 4090'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 1:30 AM Day 24 Month 9 Year 1969

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1175'.

Circulated hole with heavy mud. Pulled DP to 1400' and displaced 100 Sx. cement thru
DP from 1400' to 1075'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1969

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 9/26/69
INV. NO. 540-W

926-69