

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20160-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1968
CONSERVATION DIVISION
Wichita, Kansas
12-2-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Theodore Gore,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Schropp Well No. 1

Location CSW-SW Sec. 34 Twp. 8 Rge. (E) (W) 28

County Sheridan Total Depth 4020

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 4:30 AM Day 27 Month 11 Year 1968

The Above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 220 Sx.
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 100 Sx. cement thru
DP from 1375' to 1050'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement from
40' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 12/3/68
INV. NO. 8935-11