

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20108-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 7 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
6-5-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Imperial Oil Company,

Complete Address: 780 4th National Bank Building, Wichita, Kansas.

Lease Name Koster Well No. 1

Location CNE-NW Sec. 20 Twp. 8 Rge. (E) (W) 29

County Sheridan Total Depth 2599

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A x

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 4:00PM Day 31 Month 5 Year 1967

The Above well was plugged as follows:

241'--8 5/8" Surface pipe, cement circulated with 200 Sx.  
Top of Dakota section @ 1325'.

Circulated hole with heavy mud. Pulled DP to 1550' and displaced 100 Sx. cement thru

DP from 1550' to 1225'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from

275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 6/5/68  
INV. NO. 7891-W