

KANSAS

*JP*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20106-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 3 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Imperial Oil Company,

Complete Address: 780 Fourth National Bank Building, Wichita, Kansas.

Lease Name Selbe Well No. 1

*NW NW NE NE/4*

Location 440' FWL & 440' FNL Sec. 22 Twp. 8 Rge. 29W (EX) (W)

County Sheridan Total Depth 2570

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Above

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 12:00PM Day 28 Month 5 Year 1968

The Above well was plugged as follows:

243'--8 5/8" Surface Casing, Cement circulated with 200 Sx.  
Top of Dakota Section @ 1300'.

Circulated hole with heavy mud. Pulled pipe to 1525' and displaced 100 Sx. cement  
thru DP from 1525' to 1200'. Pulled DP to 275' and displaced 20 Sx. cement thru  
DP from 275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 6/4/68  
INV. NO. 1881-W