

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20096-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Misco Supply Company,

Complete Address: Misco Building, Wichita, Kansas.

Lease Name Edwards Well No. 1

Location SW-SW-SE Sec. 26 Twp. 8 Rge. (E) (W) 29

County Sheridan Total Depth 4360'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company, Incorporated,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 12:30 PM Day 7 Month 10 Year 1968

The Above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 200 Sx.  
4360'--4 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to  
4180'. Top perforations @ 4170'.

Sanded well back to 4150' and set 3 sx. cement with dump bailer. Pulled 4 1/2" casing  
and squeezed well with 4 sacks gel plus 5 sacks hulls then 100 Sx. cement from 1500'  
to 1175' then 22 sacks gel from 1175' to 275' and followed with 20 Sx. cement from  
275' to 215' then 4 sacks gel from 215' to 30' and finally 10 Sx. cement from 30' to  
bottom of cellar. Maximum pump-in pressure--100#. Final shut-in pressure--50#.

Mudding and cementing operations performed by Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 10/14/68

STATE CORPORATION COMMISSION

OCT 14 1968

INV. NO. 8622-4

CONSERVATION DIVISION  
Wichita, Kansas

10-14-68