

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 1 1971

CONSERVATION DIVISION  
Wichita, Kansas

11-1-71

18-179-20291-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Halliburton Oil Producing Company,

Complete Address 117 Cameron Building, Oklahoma City, Oklahoma.

Lease Name Edwards Well No. 1

Location CNW-SE Sec. 26 Twp. 8 Rge. (E) (W) 29

County Sheridan Total Depth 4100'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Chief Drilling Company, Incorporated,

Address 905 Century Plaza, Wichita, Ks. License No.       

Operation Completed: Hour 5:30 AM Day 28 Month 10 Year 1971

The above well was plugged as follows:

198'--8 5/8" Surface casing, cement circulated with 275 Sx.  
Top of Dakota section @ 1200'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 100 Sx. cement thru  
DP from 1125' to 1100'. Pulled DP to 225' and displaced 25 Sx. cement thru DP from  
225' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. G. Nichols  
Well Plugging Supervisor

DATE 11/2/71

INV. NO. 4566-W