

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20348-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1973
CONSERVATION DIVISION
Wichita, Kansas

1-22-73

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Berndt Well No. A-1

Location CSW-SE Sec. 28 Twp. 8 Rge. (E) (W) 29

County Sheridan Total Depth 4115'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated,

Address Above License No.

Operation Completed: Hour 10:45 AM Day 20 Month 1 Year 1973

The above well was plugged as follows:

226'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1225'.

Circulated hole with heavy mud. Pulled DP to 1450' and displaced 110 Cu. Ft. cement
thru DP from 1450' to 1125'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 1-22-73

INV. NO. 6886-14