

KANSAS

V
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1968

CONSERVATION DIVISION
Wichita, Kansas

15-179-20098-00-00

5-28-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Theodore Gore,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Koster Well No. 1

Location CSE-SE Sec. 29 Twp. 8 Rge. (E) (W) 29

County Sheridan Total Depth 4140

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 3:00 PM Day 25 Month 5 Year 1968

The Above well was plugged as follows:

230'--8 5/8" Surface pipe, cement circulated with 210 Sx.
Top of Dakota section @ 1225.

Circulated hole with heavy mud. Pulled DP to 1450' and displaced 100 Sx. cement thru
DP from 1450' to 1125'. Pulled Dp to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. D. Nichols*
Well Plugging Supervisor

INVOICED

DATE 5/28/68

INV. NO. 7828-W