

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1974
11-25-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Kysar Well No. 2

Location CSW/4 Sec. 17 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3875'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 10:30 AM Day 16 Month 11 Year 1974

The above well was plugged as follows:

166'--8 5/8" Surface casing, cement circulated with 165 Sx.
3875'--4 1/2" Production casing cemented on bottom with 175 Sx. Top of perforations @ 3620'.

Pushed plug to 3400', sanded back to 3350' and set 4 Sx. cement with dump bailer.

Pulled 4 1/2" casing (1770') and squeezed well initially with 5 sacks hulls and 12 sacks gel following with 110 Cu. Ft. cement from 1150' to 825' then 16 sacks gel from 825' to 185' and followed with 30 Cu. Ft. cement from 185' to 110' then 2 sacks gel from 110' to 30' and finally 10 Cu. Ft. cement from 30' to bottom of cellar. Maximum pump-in pressure-200#. FSIP-50#. (Mudding & cementing by Sun Oil Well Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickel
Well Plugging Supervisor

INVOICED

DATE 11/25/74
INV. NO. 355-W