

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1973
10-25-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Conard Well No. 1

Location CS/2-SW-NW Sec. 17 Twp. 8 Rge. (E) (W)26

County Sheridan Total Depth 3900'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 3:30 AM Day 22 Month 10 Year 1973

The above well was plugged as follows:

164'--8 5/8" Surface casing, cement circulated with 135 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 110 Cu. Ft. cement
thru DP from 1200' to 875'. Pulled DP to 185' and displaced 30 Cu. Ft. cement thru
DP from 185' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 10/25/73

Signed: W. J. D. D. D.
Well Plugging Supervisor

INV. NO. 8060-12