

KANSAS

STATE CORPORATION COMMISSION

[Handwritten mark]

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kaiser-Francis,

Complete Address 909 Palace Building, Tulsa, Oklahoma.

Lease Name Karnes Well No. 1

Location NE-SE Sec. 18 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3852'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas, License No.

Operation Completed: Hour 5:30 AM Day 31 Month 6 Year 1970

The above well was plugged as follows:

197'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 6/4/70
INV. NO. 1995-W