

15-179-20274-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1970
CONSERVATION DIVISION
Wichita, Kansas
11-10-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Landes Exploration Compsny,

Complete Address 416 Union Center Building, Wichita, Kansas.

Lease Name Taylor Well No. 1

Location SW-SW-SW Sec. 18 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3885'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Hellar Drilling Company, Incorporated,

Address 339 Union Center, Wichita, Kansas. License No. _____

Operation Completed: Hour 5:30 PM Day 7 Month 11 Year 1970

The above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru
DP from 1300' to 975'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. S. Nichols
Well Plugging Supervisor

INVOICED

DATE 11/10/70

INV. NO. 2830-W