

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1971
CONSERVATION DIVISION
Wichita, Kansas
5-10-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kaiser-Francis,

Complete Address 4120 East 51st Street, Tulsa, Oklahoma.

Lease Name Karnes Well No. 2

Location App:SW-NW-SE Sec. 18 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3716'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 1:30 PM Day 7 Month 5 Year 1971

The above well was plugged as follows:

213'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement
thru DP from 1200' to 875'. Pulled DP to 215' and displaced 25 Sx. cement thru DP
from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 5/12/71
INV. NO. 3665-W