

KANSAS

Form CP-3  
Rev. 6-26-62

GP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20038-00-00

RECEIVED  
STATE CORPORATION COMMISSION

AUG 28 1967

8-28-67

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Dane G. Hansen Trust

Complete Address: Logan, Kansas

Lease Name Taylor Well No. 1

Location SE SE SE Sec. 19 Twp. 8 Rge. 26 (E) (W) X

County Sheridan Total Depth 3900

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: C-G Drlg. co.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 9<sup>40</sup> Day 25 Month 8 Year 1967

The Above well was plugged as follows:

RTD ~~3900~~' 8 5/8 csg set at 201' cwc 150 sc.

Gunned pits, circulated heavy mud, set cementing plug at 1700' and displaced 100 sc cem.  
thru drill pipe. Heavy mud to 190' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massie  
Well Plugging Supervisor

DATE 8-29-67

INV. NO. 6973-W