

15-179-20244-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 27 1970  
CONSERVATION DIVISION  
Wichita, Kansas

3-27-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Dreiling Oil Company & Hiko Bell Mining & Oil Co.,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Pfeifer Well No. B-1

Location CNE-NE Sec. 19 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3815'

Abandoned Oil Well          Gas Well          Input Well          SWD Well          D & A X

Other well as hereafter indicated         

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.         

Operation Completed: Hour 2:30 PM Day 22 Month 3 Year 1970

The above well was plugged as follows:

179'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 950'.

~~Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru~~  
DP from 1175' to 850'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from  
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. [Signature]  
Well Plugging Supervisor

INVOICED

DATE 3-27-70

INV. NO. 1644-W