

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20351-00-00

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1973

CONSERVATION DIVISION
Wichita, Kansas

2-27-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Pfeifer Well No. A-1

Location CSW-NW Sec. 19 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3916'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 6:30 AM Day 25 Month 2 Year 1973

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated with 135 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 1250' to 925'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 1140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement from bridge to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/28/73
INV. NO. 7053-W

Signed: W. L. Deibel
Well Plugging Supervisor