

DISTRICT CONSERVATION AGENT'S REPORT

R

15-179-001a1-00-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____
LOCATION NW NW SW
SEC. 20 TWP. 8 RGE. 26

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Pfeifer _____

Operator Woodman & Iannitti Address 717 Union Natl Bldg Wichita,

Field _____ County Sheridan

Total Depth 3940 Feet.

Plugging Contractor same

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 148' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at 500', displaced 20 sax cement through drill pipe, heavy mud to 140', set cementing plug and displaced 15 sax cement through drill pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

John Pfeifer

District Conservation Agent

Date 10-5-57

RECEIVED
OCT 9 1957
STATE CORPORATION COMMISSION
WICHITA, KANSAS

0-9-57

PLUGGING
FILE SEC. 20 T. 8 R. 26W
BOOK PAGE 52 LINE 15