

KANSAS

Q STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20254-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1970
CONSERVATION DIVISION
Wichita, Kansas

6-22-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bennett & Roberts Oil Operations,

Complete Address Home State Bank Bldg., Russell, Kansas.

Lease Name C. Taylor Well No. 1

Location NW-NW Sec. 20 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3865'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 5:30PM Day 15 Month 6 Year 1970

The above well was plugged as follows:

223'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru
DP from 1175' to 850'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *R. L. Nichols*
Well Plugging Supervisor

DATE 6/22/70
INV. NO. 2078-W