

KANSAS

24

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1970
CONSERVATION DIVISION
Wichita, Kansas

11-3-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20273-00-00

Operator's Full Name Abercrombie Drilling, Inc. & Consolidated Oil & Gas, Inc.

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Mizer Well No. 1

Location CS/2-SW-SE Sec. 21 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3910'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Abercrombie Drilling, Incorporated.

Address 801 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 5:30 AM Day 1 Month 11 Year 1970

The above well was plugged as follows:

246'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1280' and displaced 50 Sx. cement thru
DP from 1280' to 1040' with 50 Sx. Pulled DP to 270' and displaced 25 Sx. cement thru
DP from 270' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 11/3/70
INV. NO. 2801-U