

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-30060-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 13 1965
4-13-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name D & D Drilling Company,

Complete Address: 307 Schweiter Building, Wichita, Kansas.

Lease Name Miser Well No. 1

Location CNE-NE Sec. 21 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3850

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 10:00PM Day 10 Month 4 Year 1965

The Above well was plugged as follows:

234'--8 5/8" Surface pipe cement circulated with 200 Sx.

Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx. cement

thru DP. Heavy mud to 220', set plug with 1/4 sack hulls and displaced 20

Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10

Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 4/13/65

INV. NO. 978-W