

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-05193-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name M. J. Bove Operating Company,

Complete Address: 75 1/2 East Wichita Avenue, Russell, Kansas.

Lease Name Pratt Well No. 9

Location NW-NW-SE Sec. 22 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3840'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Barnes & Sons Pipe Pulling Company,

Address: Box #313, Russell, Kansas. License No. 9

Operation Completed: Hour 2:30PM Day 28 Month 6 Year 1968

The Above well was plugged as follows:

277'--10 3/4" Surface casing, cement circulated with 250 Sx.  
3802'--7" OD Production casing cemented on bottom with 225 Sx. (9" Hole).  
Top perforations from 3620' to 3624'

Pushed plug to 3500', sanded to 3490' and set 5 Sx. cement with dump bailer.

Pulled 7" casing and squeezed well initially with 13 sacks gel plus 5 sacks hulls and

followed with 130 Sx. cement from 1185' to 860' then 17 sacks gel from 860' to 225'

and followed with 25 Sx. cement from 225' to 175' then 5 sacks gel from 175' to 30'

and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--

250#. Final shut-in pressure--250#. (Cementing and mudding operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION

Signed: [Signature]

JUL 1 1968

Well Plugging Supervisor

CONSERVATION DIVISION  
Wichita, Kansas

7-1-68

INVOICED

DATE 7/2/68  
INV. NO. 8016-4