

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED 10-2-68  
STATE CORPORATION COMMISSION  
OCT 2 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

15-179-20144-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name M. J. Bove Operating Company,

Complete Address: 754 East Wichita Avenue, Russell, Kansas.

Lease Name Pratt Well No. 12

Location SE-SE-NE Sec. 22 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3805

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No.     

Operation Completed: Hour 10:15 PM Day 29 Month 9 Year 1968

The Above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru  
DP from 1175' to 850'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from  
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. D. Nichols  
Well Plugging Supervisor

INVOICED

DATE 10/2/68  
INV. NO. 8565-W