

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

18-179-20313-00-00

7-3-72  
RECEIVED  
STATE CORPORATION COMMISSION  
JUL 3 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Cow Gulch Oil Company

Complete Address 909 17th St. Denver, Colorado

Lease Name Pratt "A" Well No. 1

Location C NW SE SE Sec. 22 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3855'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.     

Operation Completed: Hour 11 P Day 1 Month 7 Year 1972

The above well was plugged as follows:

RTD 3855' 8 5/8 csg set at 260' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 1150' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Lea F. Massey  
Well Plugging Supervisor

INVOICED

DATE 7-5-72

INV. NO. 5974-40