

14

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20359-00-00

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1973

CONSERVATION DIVISION
Wichita, Kansas

8-8-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Chief Drilling Company, Incorporated & Bill J. Porter,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Schaffer Well No. 1

Location CNW-SW Sec. 22 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3800'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Chief Drilling Company, Incorporated,

Address Above License No.

Operation Completed: Hour 1:00 AM Day 6 Month 8 Year 1973

The above well was plugged as follows:

223'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 110 Cu. Ft. cement
thru DP from 1150' to 825'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *K. L. J. J. J.*
Well Plugging Supervisor

INVOICED

DATE 8/8/73
INV. NO. 7921-11