

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 35-18

LOCATION NW SW SE

SEC. 23 TWP. 8 RGE. 26

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 6 Lease Pratt

Operator Musgrove Pet Corp. Address Wichita, Kans

Field _____ County Sheridan

Total Depth 3770 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 202' circulated with cement -7" at 3764' cemented.

Lane wells plugs and cement in bottom, top perforations at

3675', filled hole with chat to 3670', set 5 sax cement with

dump bailer, pulled 1810' 7" casing, filled with mud to

200', set rock bridge and 20 sax cement, filled with heavy

mud to 30', set rock bridge and 10 sax cement to bottom

cellar.

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1950

Edwin Kelly
CONSERVATION DIVISION
Wichita, Kansas
District Conservation Agent

Date 11-11-50

PLUGGING
FILE SEC 23 T 8 R 26
BOOK PAGE 35 LINE 18