

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1971
CONSERVATION DIVISION
Wichita, Kansas
1-27-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Commercial Oil Company,

Complete Address 5252 North Broadway, Wichita, Kansas.

Lease Name Pratt Well No. 7

Location CNW-NW-SW Sec. 23 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3865'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box # 364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 11:30 AM Day 23 Month 1 Year 1971

The above well was plugged as follows:

262'--10 3/4" Surface casing, cement circulated with 260 Sx.
3843'--7" OD Production casing cemented on bottom with 200 Sx. No plug back nor per-
forations indicated.

Pushed plug to 3625', sanded back from 3625' to 3600' and set 6 Sx. cement with dump
bailer. Pulled 8" casing (1000') and squeezed well initially with 6 sacks hulls and
13 sacks gel and followed with 130 Sx. cement from 1200' to 875' then 20 sacks gel
from 875' to 275' and followed with 35 Sx. cement from 275' to 200' then 7 sacks gel
from 200' to 30' and finally 15 Sx. cement from 30' to bottom of cellar. Maximum
pump-in pressure-150#. FSIP-50#. (Mudding and cementing by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. S. Nichols
Well Plugging Supervisor

INVOICED

DATE 1/28/71

INV. NO. 3264-14