

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 6 1972
7-6-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Et al, Inc.

Complete Address 119 Cameran Bldg., Oklahoma City, Oklahoma

Lease Name Pratt Well No. 1

Location SE SE NE Sec. 23 Twp. 8 Rge. 6 (E) (W) 36

County Sheridan Total Depth 2178'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated ~~Anhydrite Test~~ ?

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 4:30 P Day 4 Month 7 Year 1972

The above well was plugged as follows:

RTD 2178' 8 5/8 csg set at 245' cwc. Cmt. Mat. 50-50 poz cmt W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 1150' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Messing
Well Plugging Supervisor

INVOICED

DATE 7/6/72
INV. NO. 5996-u