

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-179-05204-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NW SW NW

SEC. 25 TWP. 8 RGE. 26 W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Fox

Operator Jones Shelburne-Farmer, Inc. Address Russell, Kans

Field _____ County Sheridan

Total Depth 3960 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 182' circulated with cement - 5 1/2" at 3960 with 100

sax cement behind - P.B. to 3830', perforated at 3755'

Filled with sand to 3740', set 4 sax cement with dump bailer.

pulled 2150' 5 1/2" - filled with heavy mud to 180', set rock and

15 sax cement, mud to 35', set rock and 10 sax cement to bottom

cellar.

Edna Betty

District Conservation Agent

Date 2-14-57

PLUGGING
FILE SEC. 25 T. 8 R. 26 W
BOOK PAGE 141 LINE 35

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1957
02-18-1957
CONSERVATION DIVISION
Wichita, Kansas