

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-00104-00-00

Operator's Full Name John O. Farmer, Incorporated,

Complete Address Box #352, Russell, Kansas.

Lease Name Pratt Well No. A-1

Location SE-SE-NE Sec. 26 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3940'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Incorporated,

Address Box #698, Great Bend, Kansas. License No.

Operation Completed: Hour 2:30 PM Day 22 Month 3 Year 1972

The above well was plugged as follows:

160'--8 5/8" Surface casing, cement circulated with--
3913'--5 1/2" Production casing cemented on bottom with 125 Sx. No plug-back indicated.
Top of perforations @ 3703'.

Pushed plug to 3675', sanded well back to 3650' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing (1230') and squeezed well initially with 5 sacks hulls and 10 sacks
gel and followed with 110 Cu. Ft. cement from 1225' to 900' then 18 sacks gel from
900' to 180' and followed with 30 Cu. Ft. cement from 180' to 100' then 2 sacks gel
from 100' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar.

(Mudding and cementing operations performed by Allied Cementing Co. Inc.,).

Maximum pump-in pressure--400#. Final shut-in pressure-100#.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 3-30-72

INV. NO. 5423-W