

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-179-65207-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 35-34

LOCATION NW NW SW

SEC. 26 TWP. 8 RGE. 26

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Coltrin

Operator Jones, Shelburne Farmer ^{unc} Address Russell, Kans.

Field _____ County Sheridan

Total Depth 3930 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 182' circulated with cement - 5 1/2" at 3900' with
100 sax cement behind - Lane Wells plugs to ~~3728~~ 3740' - perforated
at 3728'.

Filled with sand to 3700', set 4 sax cement with dump bailer,
pulled 1500' 5 1/2" - filled hole with mud to 182', set rock and
15 sax cement, mud to 35', set rock and 10 sax cement to bottom
cellar.

VED
COMMISSION

Edw. Stealy
District Conservation Agent

Date 3-14-56

APR 16 1956

03-16-1956
Wichita, Kansas

PLUGGING
FILE SEC. 26 T. 8 R. 26 W.
BOOK PAGE 35 LINE 34