

State of Kansas



15-065-20096-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1967
10-16-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jim Lahar of B & B Drilling Co., Inc., has this
date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Allison & Black,

Complete Address: 1415 Wichita Plaza, Wichita, Kansas.

Lease Name: Sutor Well No. A-1

Location: 130' East of SW-SW-NW Sec. 36 Twp. 9 Rge. (E)(W) 21

County Graham Total Depth 3574 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahar was instructed to plug the well as follows:

208'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 1025' to 1190'.

Circulate hole with heavy mud. Pull DP to 1210' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.
Pull DP, set plug @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent