



15-065-20426-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 16 1971

CONSERVATION DIVISION
Wichita, Kansas

-4-16-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clem Burton of Pickrell Drilling Company has this

date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company,

Complete Address: 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Worland Well No. A-1

Location: CNW-SE Sec. 3 Twp. 9 Rge. (E)(W) 22

County: Graham Total Depth 3838' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 650'.

Circulate hole with heavy mud. Pull DP to 875' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

M. L. Dichek
Conservation Division Agent