



13-065-20147-00-00

ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 10 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 6-10-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Paul Stevens of Omega Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Stevens guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Incorporated,

Complete Address: 410 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Rice Estate Well No. A-1

Location: NE-SE Sec. 9 Twp. 9 Rge. (E)(W) 22

County: Graham Total Depth 2580' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stevens was instructed to plug the well as follows:

223'--8 5/8" Surface pipe, cement circulated with 185 Sx.
Top of Dakota Section @ 840'.

Circulate hole with heavy mud. Pull DP to 1065' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

M. L. Pichek
 Conservation Division Agent