



15-065-20280-06-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 1 1969  
CONSERVATION DIVISION  
Wichita, Kansas

12-1-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 West Wichita Avenue, Russell, Kansas,

Lease Name: Mildrexter Well No. 1

Location: NW-NW-SW Sec. 2 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3810' Oil Well

~~Gas Well~~ ~~Input Well~~ ~~SWD Well~~ ~~D. & A.~~ X ~~Lost Hole~~

Mr. Bucheister was instructed to plug the well as follows:

167'--8 5/8" Surface casing, cement circulated with 125 Sx.  
Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 100 Sx.  
cement thru DP. Pull DP to 185' and displace 20 Sx. cement thru DP.  
Fill DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

A. L. Nichols  
Conservation Division Agent