



15-065-20731-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSION

DEC 30 1974

CONSERVATION DIVISION  
Wichita, Kansas

12-30-74

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Weber of Abercrombie Drlg. has this

date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Inc.

Complete Address: 801 Union Center, Wichita, Ks.

Lease Name: Quint Well No. 1

Location: NE NW NE Sec. 3 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3820' Oil Well

Gas Well  Input Well  SWD Well  D.-&-A.  Lost Hole

Mr. Weber was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set 70 sk cmt plug at 1130' thru drill  
pipe. Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to  
40' set solid bridge & 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Massey  
Conservation Division Agent