



15-065-20271-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 30 1969  
CONSERVATION DIVISION  
Wichita, Kansas

10-30-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Mickelson of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Mickelson guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: McVey Well No. 1

Location: NE-SE-NW Sec. 10 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3845 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Mickelson was instructed to plug the well as follows:

188'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 750'

Circulate hole with heavy mud. Pull DP to 975' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP/  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellarr.

Very truly yours,

*K. L. Dickels*  
Conservation Division Agent